



---

# Strategy for the integration of the LMJ (Laser Megajoule) control system

*J.-C. Picon, P. Bétrémieux, J.-J. Dupas, J. Nicoloso, F. Signol*  
**CEA/DAM**  
*France*

**Presented by**  
**Jean-Claude PICON**



# PRESENTATION OVERVIEW



**1. Laser Megajoule (LMJ) Facility**

**2. LMJ Control System - Industrial Policy**

**3. Integration Strategy of the Control System**

**4. Strategy Steps**


**5. LMJ control system milestones**

© Didier Fosse / G2i Vertigo



# LMJ Facility

- The Simulation program forms the basis for the guarantee of the safety and reliability of French nuclear weapons without nuclear tests.
- LMJ, a cornerstone of this program, is dedicated to studying the physics of matter at high energy densities (plasmas, nuclear fusion, etc.).
- LMJ is a laser beam system which focuses an energy  $> 1$  MJ on a tiny target.




- LMJ is been built in the Aquitaine Scientific and Technical Center (CESTA) of the CEA near Bordeaux



# LMJ Facility Overview



- ▶ Beams are grouped in quads



- ▶ Numerous sensors are positioned around the target



- ▶ Beams are grouped in bundles of 8 beams located in 4 bays (176 beams upgradable to 240)

- ▶ Control system is composed of:
  - ~ 150 servers in a computer room
  - ~ 450 PLC or rack-mounted PC next to equipment

# LMJ Control System - Industrial Policy



***A dozen major contracts correspond to the main LMJ functions***



# Integration Strategy of the Control System




## *The strategy derives from ... constraints*

- Give CEA the means to carry out numerous integrations.
- Qualify software outside the facility prior to their transfer to the LMJ:
  - Correct faults as soon as possible
  - Debug without damaging the system
  - Reduce as much as possible the LMJ activity
- Promote the independence of the subcontractors
- Integrate a new bundle in the LMJ building while using the commissioned ones

*and*

*solutions*



# Integration Strategy of the Control System



**The strategy is a 3-step process:**

**Who ?**

**Where ?**

- **STEP 1 : Factory acceptance tests**

- Acceptance tests for equipment
- Acceptance tests for control system

*Contractors*

In  
Factory

- **STEP 2 : Integration tests  
with equipment simulators**

- Global tests for the supervisory system
- Global tests for each control subsystems
- Tests of the whole control system

*CEA*

*Subsystem  
By  
Subsystem*

On  
PFI

- **STEP 3 : Functional integrations from an  
integration room with equipment**

- Industrial tests for each subsystem
- System tests of the whole process
- Bundle delivery for validation from operations control room

*Contractors*

*CEA*

*Bundle  
By  
Bundle*

In  
LMJ




# STEP 1 : Factory Acceptance Tests



## ***Internal functional tests + protocols tests + reliability tests are required***

- Subsystem Contractors in charge of all equipment and control subsystems
- Functional tests with the same LMJ configuration, despite missing equipment
  - ⇒ The contractor must build and supply equipment simulators to replace missing equipment
- Protocols tests without any subsystem in interface
  - ⇒ The interface simulators supplied by CEA implement standardized protocols and allow testing.
- Reliability tests and their automation require the two types of simulator






## STEP 2 : Integration Tests on the Integration Platform



### **Global tests + system tests are required**

- Integration contractor supplies and installs the PFI heart:
  - Network core
  - Management tools
  - Interface and equipment simulators
- High-level supervisory system is installed to perform global tests (1)
- Each control system is added and:
  - his good installation is verified (2)
  - It is integrated to the high-level supervisory system to finish the global tests (3)
- Integration contractor tests the whole control system with : (4)
  - Sequences that he has developed
  - Settings automatic computations




## STEP 3 : Functional Integrations in the LMJ building




### *The first bundle is integrated from the operations control room:*

- **Industrial tests** are performed by the contractors to check the behaviour of equipment and the wiring
- Servers are installed in a computer room and connected to the operation network
- **System tests** are then performed by CEA to make sure that all subsystems work well together



# STEP 3 : Functional Integrations in the LMJ building




***The bundles #2 to 30 are integrated from integration control room***

- New control system is connected to the integration network
- Subcontractors perform industrial tests (1)
- CEA performs system tests (2)
- And commissions from operations control room (3)



# LMJ Control System Milestones

*The challenge is to coordinate the dozen of contractors*



**Are there any questions ?**