CERN Proton Synchrotron Complex High-Level Controls Renovation


S. Deghaye, M. Arruat, D. Garcia Quintas, M. Gourber-Pace, G. Kruk, O. Kulikova, V. Lezhebokov, S. Pasinelli, M. Peryt, C. Roderick, E. Roux, M. Sobczak, R. R. Steerenberg, J. P. Wozniak, Z. Zaharieva

CERN, Geneva, Switzerland.

Agenda

- Geographical scope
- Why a renovation project?
- Injector Controls Architecture
- Project planning
- Conclusions


Geographical scope



Why a renovation project?

- No resources to maintain two parallel control systems
 - → Homogenisation needed!
- 30+ applications for the complex Many still in X/Motif
 - → Who can hire a X/Motif developer?
- Recent developments focused on LHC
 - → New features difficult to integrate in the PS complex
- PS built in 1959 & can produce a different beam every 1.2 seconds
 - → Different requirements


Previous PS control system



15-10-2009

CERN Proton Synchrotron Complex High-Level Controls Renovation S. Deghaye – ICALEPCS'09


Injector Controls Architecture



Goals & Challenges


- Reduction and stabilisation of the traffic between FECs and high-level control system
 - Distribution of acquired values to the GUIs, up to 12'000 every 1.2 seconds
- Compute once, use everywhere
 - Redesign of the applications, not just rewrite them in Java
- Work at a higher level as in LHC (machine model)
 - PS is old (1959) and difficult to model
 - Operations crew works close to the hardware

Planning



- 2007: Study the requirements => Vision
- 2008: InCA project in place, architecture validation
- 2009: Development phase + LEIR deployment
- 2010: First deployment on the PS machine
- Regular milestones: coherent set of features & operational validation.

Iterative developments



- Planning approach: iterative developments + regular operational validation.
- Demo in front of the team and the user representatives
- Machine Development → replace the current controls system for few hours (full scale tests)

Conclusions

- InCA: homogenisation of the High-Level Controls
 - Reuse of LHC components/systems
 - Keep the specificities of the PS Complex
- Project well on the way
 - Several successful validations on the PS machine
 - Successful deployment for LEIR 2009 run (simplified version)
 - First target in the PS: Q3 2010
- Iterative planning approach
 - Operational validation every 3-4 months
 - 3-4 weeks development sprint ended with demo

Questions?!?

Thank you for your attention!